# Safety & Quality in Projects

**Dedicated Freight Corridor Corporation of India Ltd.** 

11th Sep 2023 | Safety and Quality Forum, New Delhi



# A Rupee Spent Is Spent ......





A **Second** gone is gone ......

Do it right the first time



#### Contents




Three Pillars of Health and Safety Management

Safety Scenario at DFC Project

Steps to enhance safety at DFC Worksites

## Three Pillars of Health and Safety Management







## 34 Million Accidents Occur Worldwide Every Year

(International Labor Organization)

Accidents can cause a great deal of pain and suffering.

It brings anguish not only to the injured, but also to their co-workers, family members, relatives, and many others.

**Everything** that can be done to avoid this needs to be done.



Employers have an obligation to ensure that their employees do not suffer injury, ill health, or pain.



In developing countries, employers need to be more aware about safety and health of their employees.

#### Financial Reason





If an accident occurs, the organization will suffer a great deal of damage.

# US \$ 3 trillion are lost each year due to injuries, illnesses and fatalities (International Labor Organization)

The costs can be enormous, many times greater than most individuals think


#### Financial Reason



#### Covered by insurance (visible cost)

- Workplace accident insurance
- Third party insurance
- Construction insurance

Not covered by insurance (Hidden costs)



Data shows that the actual costs are 8 to 36 times higher than the direct costs.

(UK)



- Decline in productivity
- Overtime work for employees
- Leave compensation
- Temporary employment
- Accident investigation
- Fines
- Increase in insurance premium rates
- Loss of company's credibility
- Decline in stock price
- Loss of customers

#### Legal Reason



#### **Occupational Health & Safety Regulation**

- Most countries have laws and regulations
- To ensure the health and safety of workers.
- Organizations/agencies oversee and enforce that these laws and regulations

Health and safety requirements are clearly stated in the contract documents for infrastructure projects.

#### **Indian Scenario**

Industrial Safety and Health (Ministry of Labour & Employement)

National Occupational Safety and Health (OSH) framework

**Legal Action** 

## Safety and Health Management System



PDCA	ISO 45001	Implementation	Management Tools
	Leadership	Top management declares its commitment to health and safety management.	Health and Safety Policy
PLAN	Plan	Identify hazards and analyze risks.  Prepare health and safety management plan and construction plan based on health and safety policy.	<ul> <li>Health and Safety Management Plan</li> <li>Construction plan</li> <li>Hazard and risk analysis</li> </ul>
DO	Support and operation	Provide the necessary resources and implement the plan Provide education and training for employees and workers Top management demonstrates its commitment to health and safety management.	<ul> <li>Training for newcomers</li> <li>Periodic Health Examination</li> <li>Work Permit</li> <li>Health and safety committee meetings</li> <li>Health and Safety Management Report</li> </ul>
СНЕСК	Performance Evaluation	Ensure that work is carried out in compliance with plans, contracts, and laws and regulations.	<ul> <li>On-site health and safety inspections</li> <li>Internal and external health and safety audits</li> <li>ISO 45001 audits</li> </ul>
ACTION	Kaizen (constant improvement)	Implement measures to prevent recurrence based on accident investigation reports. Review and continuously improve the safety and health management plan.	<ul> <li>Accident Investigation Report</li> <li>Compliance report</li> <li>Update of construction plan and health and safety management plan</li> </ul>



# Safety Scenario at DFC Project

#### SAFETY TARGETS, GOALS & AIMS IN DFC PROJECT



DFCCIL has defined "Safety targets, goals and aims" in their works by implementing effective safety and health techniques and measures to achieve -

- Zero total recordable injury or accident.
- Zero reportable environmental incident.
- All personnel inducted in accordance with the approved contractor's Safety Plan.
- Total compliance of conducting inspections and audits as per approved Safety plan.
- 100% incident / accident recording and reporting.
- 100% adherence of usage of appropriate PPEs at work.
- Executing construction work with least disturbance to the environment, road/rail users, nearby residential areas and traffic.

#### KEY SAFETY RISKS IN DFC PROJECT



- Working adjacent to Live IR Tracks
- Working adjacent to high tension lines
- Working near and over Water
- Working in Tunnel/Deep cut
- Heavy Lifting & Launching Operation
- Working at Height
- Moving Equipment/Machinery- Rail bound & Road bound
- OHE Mast Erection, Boom Erection, Stringing of wire
- Loading/Unloading of Construction Materials at Worksite


## Incident Management Through Safety Statistics




#### [Case study of WDFC Phase-2: Vadodara-JNPT (550 km)]

Safety Statistics ( 2019-2023)							
Year	Total Nos. of Man-hrs. Worked (Mn-hrs)	No. of Fatal Incident B	No. of Lost Time Injury (Days)	No. of Man-days lost (Injury & Absenteeism	Occupational Disease E	Frequency Rate F (C/A X Mn)	
2019-20	16.3	0	1	10	0	0.061	
2020-21	23.1	0	3	83	0	0.13	
2021-22	27.4	0	4	162	0	0.146	
2022-23	21.7	0	2	49	0	0.09	

#### No. of Man-Hrs. Worked



#### **Frequency Rate**





## Steps to enhance safety at DFC Worksites

## Major Cause of Accidents/Quality Issues



- Competitive bidding- Contractors want to reduce the cost
- EPC contracts- Design is a major issue
- All attention for project progress- Least attention to EHS issues
- Safety as an organizational culture lacking
- Method statements are not adhered to
- Lack of supervision and devotion of PMC agencies
- Lack of Training- For supervisory and working staff
- Inadequate availability of safety equipments and PPE kits

#### Key Safety Measures



#### ✓ Hazard Identification & Risk Assessment For Each Activity

## ✓ Regular Safety Inspections

Inspections as per Mandatory Checklists of Safety Equipment bring used

#### ✓ Mass Tool Box Talk

Discussion on Safety Measures and Procedure before start of work,

#### ✓ SHE Committee Meeting

- Regular meetings to discuss and analyse Safety Issues at Site for Implementing Safety Measures
- Stakeholder meeting to discuss Key Safety Concerns and implementation of Safety Policy guidelines in the Project

#### Key Safety Measures



#### ✓ SHE Training

Onsite Safety Awareness training to the Workers

#### ✓ MARS (Monthly Audit Rating Score)

Internal Monthly Audit between Engineer and Contractor

#### ✓ Mock Drills

 Hands on training of the Workers to demonstrate the response to Safety Incidents

#### ✓ External Health Checkup Camps

 To ensure the Physical and Mental fitness of the Workers at the Workplace and Labour Camps



# Safety Measures at DFCCIL

## **Construction Railway Operations (CRO) Training & Awareness**

Training and Awareness on "Safety Precautions" as per CRO Manual organized regularly in all Contract

Documentation work for "Construction Railway Operations (CRO) Manual" is fixed.

- Packages.
  - Constant meetings conducted by PMC/DFCC with the Contractors to sensitize and make them understand on the importance of CRO.



## Ongoing Practice on Information Dissemination on Incident (Fatal & non-Fatal) Case Studies

- "SAFETY ALERTS" are regularly issued to the Contractors as proactive measures to avoid recurrence of any incident at sites.

Information pertaining to "Derailment of Works Train" on DFC Track happened in the past is being reviewed & analysed and accordingly

shared with the Contractors to take necessary preventive measures.

#### Continuous Efforts on Safety Precautions for Contractor's Activities Adjacent to IR Live Tracks

Implementation of various safety precautions before commencement and during construction work is

- constantly enforced to the Contractors. Some of these measures are:
- Erection and Maintaining barricades/fencing as per requirements
- Work Permit from IR Training of Workers / Employees
- Look out man / Hooter




Movement of Construction Vehicles restricted within 3.5 m from IR Track.

[Barbed wire fencing b/w IR and DFC]



#### Working within 3.5 - 6 meter from nearest IR Track





# Continuous Enhancement of Safety Precaution for Machinery Working Near IR Track



- Dumping work is going in presence of PMC Engineer/ Site Supervisor/Safety Officer.
- Flagman deputed with Red flag and whistle to alert driver when train approaching.
- Demarcated with Caution tape to keep dumper away from IR Track at safe distance.
- Driver having valid Driving License & Competency Certificate.



#### Sensitization Of Contractor's Safety And Execution Team On Track Safety



- Construction Railway Operation & Track Access Procedure
- Continuous meetings with the Contractors and interface contractors to sensitize them on track safety.
- Contractors encouraged to Conduct Public outreach and public awareness Programme, which are regularly monitored by PMC



#### Safety Precautions while working near and Over Water



















#### Training & Education | Capacity Building





Safety Induction by SHE Director to JICA team



On site training by external agency



Pre deployment safety induction



Work at height safety training



Fire fighting training



Daily pre start TBT

#### Internal Site SHE Inspections










- Inspections (conducted jointly with site execution, P&M, Admin and SHE Team)
- Pre-designed checklists are used

#### **Toolbox Talks**







- Toolbox Talks at all working locations by the site engineer, supervisor & SHE personnel
- Daily before starting of physical work activities at the worksites.
- Include safety precautions followed by a Safety pledge.

#### SHE Induction Training And Awareness Training







- Mandatory for all the employees, operators, visitors & workmen before deploying
- Includes hazards & control measures, occupational health awareness and environmental & emergency response arrangements at the worksites.





#### **SHE Awareness training:**

- On Job training for specific / Hazardous work activities
- Site personnel & workmen regularly updated.

## Project SHE Committee Meeting







- Project level SHE Committee at the EMP-4 Project
- Monitoring & improvement of SHE performance monthly
- Building-up a high-level of safety culture at the various worksites
- Top management of SLT, PMC, DFCC & Sub-contractors are the members

## MARS & Monthly Electrical Safety Audit





#### **Monthly Audit Rating Score (MARS):**

- MARS Audit conducted jointly by L&T and PMC / DFCC SHE team
- Pre-designed & approved checklist
- Frequency monthly
- Implementation of various parameters of the OH & S management systems like SHE Management, Site Safety, Occupational Health & Welfare and Environmental Management checked



#### **Monthly Electrical Safety Audit:**

- Monthly Electrical Safety Audit is also conducted jointly by L&T and PMC / DFCC
- Pre-designed & approved checklist
- Frequency monthly

#### **External SHE Audit**









- Audit conducted by ISO certified external professional agency (M/s Salus EHS Solutions Pvt. Ltd.)
- Frequency of audit quarterly
- Guidelines of ISO, ILO and national standards are followed.

## Mock Drills









- Mock drills on various potential emergencies conducted monthly
- Schedule prepared on various emergencies to be tested

## Health Check-up









- Basic health check-ups (BP, SPO2 monitoring) for site staff and workmen
- Government hospital doctors checking the health condition of workmen monthly at worksites.

#### SAFETY MEASURES: DON'TS






Without shoes in switching yard




Do not wear loose cloths e.g. kurta pazama, lungi, etc.

## SAFETY MEASURES: DOs and DON'Ts








## SAFETY MEASURES: DOs and DON'Ts







## SAFETY MEASURES: DOs and DON'TS









Do not leave unwanted materials in switching yard


## Corrective Actions For Repetition



- Providing of Protection Screens to Prevent Human touching the high-voltage live OHE
- Daily Toolbox Training for Workers; Proper counselling on Fixing/Removal of Discharge Rods
- Impromptu inspection at the Site on Implementation and following of Safety Guidelines
- Health check up for Physical and Mental Readiness



## **Thank You**



## Key Challenges for Control of Safety Risks (in DFC Project)



1.	Enhanced Work Progress	Dynamic Working Conditions due to Multiple Activities, Multiple Work Fronts, Simultaneous
		Presence of Interface Contractors, Short Planning of work, Both Day & Night Working, etc. all
		posing new challenges everyday.
2.	Sheer Volume	Inherent Safety Risks during Movement & Working of Construction Machinery and Vehicles
		along Running IR Track
3.	Large Activity vs. Small / Isolated	More Safety Focus on Large Activities [such as Hill cutting, Girder Launching, etc.] as compared
	Activity	to Less Safety Focus on Small / Isolated Activities [such as dumping by dumper, working of TM,
		working of Excavators, etc.]
4.	Less Sharing of Near Miss or	Missed opportunities to learn – where we went wrong or what better can we do next time to
	Dangerous Occurrence Cases as well as	keep ourselves safe from more serious consequences.
	Case Studies from Work Sites	

## Key Challenges for Control of Safety Risks (in DFC Project)



5	Comprehensive Safety Check Points	Difficult to follow and cannot be made so many 'Yardsticks' for Safety Control.
	for Construction Machinery &	
	Vehicle	
6	Frequent Changes of Workers /	Difficult to Control. No option but to accept this fact as a Challenge.
	Drivers / Operators	

#### [RISK MANAGEMENT]

- A. Risk Assessment & Analysis to be constantly applied and updated on a regular basis to address issues arising on DFC Construction sites in order to eliminate or reduce the level of its risk (*acceptable level*) by adding safety precautions or control measures.
- B. Re-emphasize and re-strengthen the importance of Safety as a part of culture & awareness at the Field-level.